

Electric Vehicle Buyer Guide: Tesla Roadster Checklist

(A) Pre-pickup items		
	Check all of paperwork for the correct name and address for all buyers. Confirm the actual vehicle's VIN matches all of your paperwork. Verify that the vehicle's body color, interior, options, and wheels match what you configured.	
	Bring proof of down payment having been made if sent before, and the final payment, if required.	
	Bring a printed insurance card if possible, if not, bring a digital copy. Call pickup location to confirm vehicle is on-site (no delay in shipping). Check for any outstanding recalls Here	
(B)	Exterior inspection	
	Inspect body exterior paint for defects.	
Ш	Inspect under the car for signs of damage or scratches from test drives or transport.	
	Check along all body panels for gaps or misalignment, especially the trunk gap, door gap, and general fender gaps.	
	Inspect all glass. It should look clear with no damage. If the vehicle is equipped with the double pane glass, check for distortion at different levels.	
	Check for proper windshield trim installation.	
	Check for discoloration / rainbow hue of surrounding trim.	
Ц	Test all doors to ensure they open and close easily.	
	Confirm the charge port can be opened from the outside with the vehicle unlocked.	
	Check edges of the spoiler for any signs of separation from the body.	
	Check all exterior lights and cameras for condensation.	
	Inspect all-weather seals around door gaps and windows for damage and fitment. Confirm the correct number of key cards/keys come with the vehicle.	
	Test unlocking and locking of vehicle the key cards/keys.	



	Check the tires for any signs of wear or damage Check tire pressure to make sure it's within recommended PSI	
	Check the underbody for any signs of rust or damage	
(C) In the driver's seat		
	Verify the vehicle is charged at 80%+ (if required for travel to home destination). Check for any error lights on the gauge cluster. Confirm proper VIN and Spec. Check each window operation for speed and any noises. Make sure heat and air conditioning work at full power. Be sure to move air vents	
	all around and follow the airflow to confirm proper function. Make sure heated seats are working. Test the sound system to ensure all speakers are working, including the amplifier if	
	equipped. Adjust the vehicle your steering wheel and mirror adjustments. Confirm that both are working and have full movement.	
	Test vehicle's horn. Check windshield for distorted view. Try this from the drivers and passenger's seat.	
	Test the windshield wipers. Test the turn signals. Check sun-visor operation.	
	Check the rearview mirror for clarity. Confirm the keycards/keys start the vehicle.	
	Confirm that you can open and close the front compartment and trunk. Test the breaks for any sign of wear and proper function	
(D) Interior inspection		
	Inspect interior upholstery and all surfaces for damage or issues with build. Check the windshield and windows for cracks, chips or distortion. Check all seat belts for proper operation and condition.	
	Check seats for noises and all directions of adjustment.	



(E) Connectivity inspection		
Confirm iPod connection is properly functioning Confirm Cigarette lighter functionality		
(F) Lighting inspection		
 Check front lights. Check dome light. Check driver & passenger door puddle lights. Check all door lights. Check headlights (low & high beam). Check front and rear turn signal lights. Check brake lights. 		
(G) Inspect charging ability		
 Check that the charge port door opens and latches correctly. Check charge port indicator light, if equipped Test charger on site. 		
(H) App setup and final items		
 Verify any additional items that were specified as being included with purchase. Mobile charger Floor mats Adapters 		

Disclaimer: Electric Vehicle Buyer Guides provided by EV Universe are for educational purposes only and do not constitute advice on the acceptability, performance, pricing or any other factor of the purchasing experience of a vehicle.